BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/01/2018-19 Dated: 04-09-2018

APPROVED TENDER SCHEDULE –'B'

Item No: 01

Name of Work: Providing Temporary Immersion Tank for lord Ganesh Idols at near Yelahanka lake in ward No:2 of Yelahanka Sub Division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri P RAVICHANDRA	
				Rate	Rate in Words
1	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2016-17	Cum	517.50	305.49	Rupees Three Hundred Five and Paise Forty Nine Only
2	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 130 (SR 2016-17)	Cum	517.50	95.16	Rupees Ninety Five and Paise Sixteen Only
3	Code 0516-Providing Plastic Sheet (Page No xxvi/ I.768 PWD SR 2016-2017	Sqm	778.00	6.48	Rupees Six and Paise Forty Eight Only
4	Engaging Unskilled heavy Mazdoor labour for guarding and for helping the public to immersion tank Ganesh idols and to safe guard the public duging the pooja Time (including Expert swimmers) Page No LIV Sl No 5 SR 2016-17	Days	143.00	244.43	Rupees Two Hundred Forty Four and Paise Forty Three Only
5	Supply of water Through water tank for filling Tank	Earch	145.00	359.82	Rupees Three Hundred Fifty Nine and Paise Eighty Two Only
6	Providing stone dust to approach road and near immersion tank for levelling and to protect not to sliping SI No 50 Code 400 metal Component PWD SR page No II SR 2016-17	Cum	78.88	80.96	Rupees Eighty and Paise Ninety Six Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri P RAVICHANDRA	
				Rate	Rate in Words
7	Hire Charges for two Tier Barricading with casurens poles at 2.50mtrs C/C vertically and 1.50 mtrs C/C Horizontaly with Necessary earth work and labour (steel baricading)	Sft	8800.00	10.00	Rupees Ten and Paise Ninety Nine Only
8	Hire charge for Armless Plastic Chairs	Nos	1100.00	3.90	Rupees Three and Paise Ninety Only
9	Hire charge for wooden Table of size 6ft x2ft	Nos	220.00	14.99	Rupees Fourteen and Paise Ninety Nine Only
10	Hire charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire (KPWD SR 2010-11 P.55/I.6 IIIb)	Mtrs	3509.00	9.00	Rupees Nine Only
11	1321 Hire charge of 100 KVA generator including operator, Fuel transportation and Handling charges (PWD SR 2013-14(PXXXX /I.92) code No 132	Hrs	88.00	494.75	Rupees Four Hundred Ninety Four and Paise Seventy Five Only
12	Hire Charges for Shamiyana side wall of 8ft hight (Size 15ftx20ft=300sqft)	Rft	3080.00	2.00	Rupees Two Only
13	Hire charge for Shamiyana with Necessary Bambo Poles Erection Charges Including transportation (Size 15ftx20ft=300sqft)	Sft	3080.00	5.00	Rupees Five Only

Ravichandra.P
Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.